

S. Bdy. of T. 1 S., R. 35 E., W.M.

Chains		Feet
	<p><math>\frac{1}{4}</math> S., B.T.</p> <p>A fir, 14 ins. diam., brs. S.48°W., 24 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>Ascend.</p>	
45.00	Descend through dense forests of timber and undergrowth, with fallen timber.	
78.20	A dry creek, course N.10° W.	
	Ascend.	
80.00	Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, on table land, thickly set with black pine timber and spruce undergrowth for Cor. to Secs. 2, 3, 34 & 35, marked	
	T.1 S., S.35 on N.E.	
	R.35 E., S.2 on S.E.	
	T.2 S., S.3 on S.W. and	
	S.34 on N.W. faces with	
	2 notches on E. edge and	
	4 notches on W. edge,	
	from which,	
	A pine, 10 ins. diam., brs. S.56° W., 17 lks. dist., marked T.2 S., R.35 E., S.3, B.T.	
	A pine, 9 ins. diam., brs. S.42° E., 21 lks. dist., marked T.2 S., R.35 E., S.2, B.T.	
	A pine, 11 ins. diam., brs. N.16° W., 19 lks. dist., marked T.1 S., R.35 E., S.34, B.T.	
	A pine, 9 ins. diam., brs. N.17° E., 19 lks. dist., marked T.1 S., R.35 E., S.35, B.T.	
	Land; high, broken and mountainous.	
	Soil; gravelly, 3rd rate.	
	Timber; fir, tamarack and pine.	
	W. on a true line bet. Secs. 3 & 34.	
	Var. 19°40' E.	
	Ascending through heavy timber.	
25.00	Descend through underbrush of yew timber.	
	Ascend.	