

East Bdy., T. 1 S., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 13 & 18.	
	Var. 20° E.	
	Ascend.	
9.50	A point of rock.	
20.00	Summit of hill, course N.W. and S.W.	
	Descend through dense timber and windfalls.	
40.00	Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground, on hillside sloping E., in dense timber and underbrush, for ¼ Sec. Cor., marked ¼ S. on E. & W. faces.	
	A spruce, 11 ins. diam., brs. S. 66° E., 8 lks. dist., marked ¼ S., B.T.	
	A tamarack, 10 ins. diam., brs. S. 38° W., 24 lks. dist., marked ¼ S., B.T.	
	Ascend through thicket of young timber.	
44.00	Leave thicket and descend through heavy timber.	
80.00	A fir tree, 13 ins. diam., which I marked for Cor. to Secs. 7, 12, 13 & 18.	
	T. 1 S., S. 7 on N.E.	
	R. 36 E., S. 18 on S.E.	
	R. 35 E., S. 18 on S.W.	
	S. 12 on N.W. faces with	
	4 notches on S. and	
	2 notches on N. edges, from which	
	A fir, 11 ins. diam., brs. S. 10° W., 17 lks. dist., marked T. 1 S., R. 35 E., S. 13, B.T.	
	A fir, 10 ins. diam., brs. S. 83° E., 14 lks. dist., marked T. 1 S., R. 36 E., S. 18, B.T.	
	A fir, 10 ins. diam., brs. N. 13° E., 17 lks. dist., marked T. 1 S., R. 36 E., S. 7, B.T.	
	No other tree in limits ; made mound of stone alongside.	
	Land; high, broken and mountainous.	
	Soil; rocky, 3rd rate.	
	Timber; pine, fir and tamarack.	
	N. bet. Secs. 7 & 12.	
	Var. 20° E.	