

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains 80.00		Feet
	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 23, 24, 25 &amp; 26, marked</p> <p style="padding-left: 40px;">T.1 S., R.35 E., S.24 on N.E. T.1 S., R.35 E., S.23 on N.W. S.26 on S. and S.23 on S.E. faces with 2 notches on S. and 1 notch on E. edges,</p> <p>from which,</p> <p style="padding-left: 40px;">A pine, 9 ins. diam., brs. N.18°E., 8 lks. dist., marked T.1 S., R.35 E., S.24, B.T. A pine, 10 ins. diam., brs. N.28°W., 11 lks. dist., marked T.1 S., R.35 E., S.23, B.T. A pine, 12 ins. diam., brs. S.67°W., 22 lks. dist., marked T.1 S., R.35 E., S.26, B.T. A pine, 14 ins. diam., brs. S.73°E., 25 lks. dist., marked T.1 S., R.35 E., S.25, B.T.</p> <p>Land; high and mountainous. Soil; 2nd rate. Heavily timbered with fir, tamarack and pine. Dense undergrowth of fir, tamarack, pine and mountain laurel.</p>	
	<p>E. on true line bet. Secs. 24 &amp; 25</p> <p style="text-align: right;">Var. 18°30' E.</p> <p>Gradual ascent.</p> <p>3.76 Old Emigrant road brs. N. &amp; S. 5.50 Top of hill brs. N.W. &amp; S.E., 75 ft. above Sec. Cor. 8.30 Descend hill, brs. N.W. &amp; S.E. 24.75 Ravine course N., 250 ft. below top of hill and ascend. 35.00 Enter opening, brs. N. &amp; S. 39.00 Top of ridge, brs. N. &amp; S., 200 ft. above ravine. 40.00 Set basalt stone, 18 x 12 x 7 ins., 12 ins. in ground, for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> on N. face, from which, A pine, 12 ins. diam., brs. S.55°W., 69 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	