

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	ascend.	
41.00	Leave clearing of right of way, brs. N.40°W. & S.40°E.	
55.50	S.S.Cronk's house brs. S.65°E. and old road brs. E. & W., 150 ft. above $\frac{1}{4}$ Sec. Cor.	
73.80	Intersect S. Bdy. of Tp., 2834 lks. W. of Cor. to Secs. 1 and 2, which is a post, 4 ins. sq., marked, T.1 S., S.36 on N.E. R.35 E., S.1 on S.E. T.2 S., S.2 on S.W. and S.35 on N.W. faces, with 1 notch on E. and 5 notches on W. edges, from which A pine, 12 ins. diam., brs. S.21°E., 14 lks. dist., marked T.2 S., R.35 E., S.1, B.T. A pine, 9 ins. diam., brs. S.5°W., 22 lks. dist., marked T.2 S., R.35 E., S.2, B.T. A pine, 13 ins. diam., brs. N.2°W., 12 lks. dist., marked T.1 S., R.35 E., S.35, B.T. A pine, 9 ins. diam., brs. N.82°E., 28 lks. dist., marked T.1 S., R.35 E., S.36, B.T. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 35 & 36, marked C.C. on N. T.1 S., R.35 E., S.36 on E. and T.1 S., R.35 E., S.35 on W. faces, with 1 notch on E. and 5 notches on W. edges, from which, A fir, 16 ins. diam., brs. N.60°E., 25 lks. dist., marked C.C., T.1 S., R.35 E., S.36, B.T. A fir, 15 ins. diam., brs. N.48°W., 24 lks. dist., marked C.C., T.1 S., R.35 E., S.35, B.T. A fir, 8 ins. diam., brs. S.48°E., 26 lks. dist., marked C.C., T.1 S., R.35 E., S.2, B.T. Land; high and mountainous.	