

Subdivisional Lines, T.1 S., R.35 E., W:M.

Chains		Feet
	S. bet. Secs. 22 & 23. Var. 19°30' E.	
2.00	Enter Creek bottom brs. N.E. & S.W. 75 ft. below Sec. Cor.	
12.00	Dry bed of Meacham Creek, 20 lks. wide, course N.E.	
13.81	Old wagon road, brs. E. & W.	
16.37	" " " " N.E. & S.W.	
18.80	Dry gulch, course W.	
20.40	Enter clearing of right of way, brs. N.20°E. & S.20°W.	
22.76	Intersect Railroad Survey from Umatilla to Baker City, brs. N.20°E & S.20°W. Location stake No. 148 † 50 on line 70 ft. above last gulch.	
24.46	Leave clearing of right of way, brs. N.20°E & S.20°W.	
31.40	Enter opening, brs. E. & W.	
35.25	Leave opening and enter timber, brs. N.W. & S.E.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., 70 ft. above Railroad Survey, marked $\frac{1}{4}$ S. on W. face, from which, A pine, 10 ins. diam., brs. N.75°E., 37 lks. dist., marked $\frac{1}{4}$ S., B.T. A spruce, 5 ins. diam., brs. N.52°W., 8 lks. dist., marked $\frac{1}{4}$ S., B.T.	
49.50	Dry gulch, course N.W.	
56.50	Top of low ridge, brs. N.W. & S.E. 100 ft. above dry gulch Descend.	
64.00	Dry bed of creek, 3 lks. wide in ravine, course N.W., 150 ft. below top of ridge, and ascend.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 22, 23, 26 & 27- 200 ft. above bed of Creek, marked T.1 S., R.35 E., S.23 on N.E. T.1 S., R.35 E., S.22 on N.W. S.27 on S.W. and S.26 on S.E. faces, with 2 notches on S. and 2 notches on E. edges, from which, A tamarack, 10 ins. diam., brs. N.37°E., 17 lks. dist., marked T.1 S., R.35 E., S.23, B.T.	