

Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains		Feet
	S. bet. Secs. 34 & 35. Var. 24° E.	
10.55	Tie road brs. N.E. & S.W.	
12.40	Wagon road to Big Meadows brs. N.20° E., S.20° W.	
13.95	Same road to Big Meadows from right of way brs. N.20° W. & S.40° E.	
21.60	Tie road brs. N.E. & S.W.	
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 200 ft. above last Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A spruce, 8 ins. diam., brs. N.54° E., 67 lks. dist., marked $\frac{1}{4}$ S., B.T. A spruce, 10 ins. diam., brs. S.22° W., 12 lks. dist., marked $\frac{1}{4}$ S., B.T.	
74.50	Intersect S. Bdy. of Tp., 2857 lks. W. of Cor. to Secs. 2 and 3, which is a post, 4 ins. sq., marked T. 1 S., R. 35 E., S. 3, with T. 1 S., S. 35 on N.E. R. 35 E., S. 2 on S.E. T. 2 S., S. 3 on S.W. and S. 34 on N.W. faces, with 2 notches on E. and 4 notches on W. edges, from which, A pine, 18 ins. diam., brs. S. 56° W., 17 lks. dist., marked T. 2 S., R. 35 E., S. 3, B.T. A pine, 9 ins. diam., brs. S. 42° E., 21 lks. dist., marked T. 2 S., R. 35 E., S. 2, B.T. A pine, 11 ins. diam., brs. N. 15° W., 19 lks. dist., marked T. 1 S., R. 35 E., S. 34, B.T. A pine, 9 ins. diam., brs. N. 17° E., 19 lks. dist., marked T. 1 S., R. 35 E., S. 35, B.T. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 34, & 35., 250 ft. above last $\frac{1}{4}$ Sec. Cor., marked C.C. on N. T. 1 S., R. 35 E., S. 35 on E. T. 1 S., R. 35 E., S. 34 on W. faces, with	