

## Subdivisional Lines, T. 1 S., R. 35 E., W.M.

Chains

Feet

2 notches on E., and

4 notches on W. edges, from which,

A fir, 10 ins. diam., brs. N.47° E., 23 lks. dist.,  
marked C.C., T.1 S., R.35 E., S.35, B.T.

A spruce, 7 ins. diam., brs. N.38° W., 11 lks. dist.,  
marked C.C., T.1 S., R.35 E., S.34, B.T.

A spruce, 8 ins. diam., brs. S.43° W., 23 lks. dist.  
marked C.C., T.2 S., R.35 E., S.3, B.T.

Land; high and mountainous.

Soil; 2nd rate.

Heavily timbered with fir, spruce, tamarack and pine.

Dense undergrowth of fir, spruce, tamarack, pine and yew.

Oct. 5th, 1882.

From the Cor. to Secs. 9, 10, 15 & 16, which is a post,  
rotten and decayed, in mound of earth, which I re-es-  
tablished by setting a new post, 4 ft. long, 4 ins. sq.  
24 ins. in ground, for Cor. to Secs. 9, 10, 15 & 16,  
marked,

T.1 S., R.35 E., S.10 on N.E.

T.1 S., R.35 E., S.9 on N.W.

S.16 on S.W. and

S.15 on S.E. faces, with

4 notches on S. and

3 notches on W. edges, from which,

A pine, 7 ins. diam., brs. N.26° E., 148 lks. dist.,  
marked T.1 S., R.35 E., S.10, B.T.

A pine, 7 ins. diam., brs. N.50° W., 41 lks. lks. dist.,  
marked T.1 S., R.35 E., S.9, B.T.

A pine, 8 ins. diam., brs. S.56° W., 28 lks. dist.,  
marked T.1 S., R.35 E., S.16, B.T.

A pine, 9 ins. diam., brs. S.67° E., 190 lks. dist.,  
marked T.1 S., R.35 E., S.15, B.T.

I run

S. bet. Secs. 15 &amp; 16.

Var. 21° E.