

Subdivisional Lines, T. 1 S., R.35 E., W.M.

| Chains | | Feet |
|--------|---|------|
| 6.08 | Creek, 5 lks. wide, runs N.W. | |
| 21.50 | " " " " " N.W.E. | |
| 22.10 | " " " " " N.W. | |
| 23.40 | Bed of same creek, 8 lks. wide, course N.E. | |
| 23.90 | " " " " " " " " N.W. | |
| 25.00 | " " " " " " " " N.E. | |
| 30.00 | Leave level flat, brs. N.E. & S.W. and gradually ascend. | |
| 37.80 | Tie road, brs. N.65°W & S.65° E. | |
| 40.00 | <p>Set post, 3 ft. long; 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., 50 ft. above flat, marked $\frac{1}{4}$ S. on W. face, from which,</p> <p>A pine, 5 ins. diam., brs. S.42°W., 38 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A pine, 34 ins. diam., brs. S.77° E., 104 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> | |
| 70.50 | Enter opening, brs. N.W. & S.E. | |
| 78.80 | Leave opening and enter timber, brs. E. & W. | |
| 80.00 | <p>Set post, 6 ins. sq., 24 ins. in ground, for Cor. to Secs. 15, 16, 21 & 22, 150 ft. above $\frac{1}{4}$ Sec. Cor., marked</p> <p>T.1 S., R.35 E., S.15 on N.E.</p> <p>T.1 S., R.35 E., S.16 on N.W.</p> <p>S 21 on S.W. and</p> <p>S.22 on S.E. faces, with</p> <p>3 notches on S. and E. edges, from which,</p> <p>A fir, 30 ins. diam., brs. N.35° E., 8 lks. dist., marked T.1 S., R. 35 E., S. 15, B.T.</p> <p>A fir, 15 ins. diam., brs. N.18° W., 20 lks. dist., marked T.1 S., R.35 E., S. 16, B.T.</p> <p>A fir, 15 ins. diam., brs. S.26°W., 17 lks. dist., marked T.1 S., R.35 E., S.21, B.T.</p> <p>A fir, 24 ins. diam., brs. S.54° E., 21 lks. dist., marked T.1 S., R.35 E., S.22, B.T.</p> | |
| | Land; high and mountainous. | |
| | Soil; 2nd and 3rd rate. | |
| | Heavily timbered with pine, fir, tamarack and spruce, | |
| | 41.70 chs. | |