

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	<p>marked C.C., T.2 S., R.35 E., S.4, B.T.</p> <p>Land; high and mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack, 72.60 chs.</p> <p>Dense undergrowth of pine, fir and tamarack.</p> <p style="text-align: right;">Oct. 7th, 1882.</p>	
	<p style="text-align: center;">General Description.</p> <p>The land in this Tp. is high and mountainous, generally heavily timbered with fir, tamarack, pine and spruce of good quality and dense undergrowth of same.</p> <p>The Baker City branch of the Oregon Railway and Navigation Co.'s Railroad and Foster toll road, extends through the Tp. and many claims have been taken.</p> <p>The soil along Meacham Creek and its tributaries and on Brown Meadows in the S.E. part of the Tp. is 1st rate. Remainder 2nd and 3rd rate.</p> <p>There is one settler living on Brown Meadows in Sec. 36.</p> <p>The Tp. is made fractional by the Umatilla Indian Reservation, the Bdy. of which runs diagonally through it.</p>	
	<p>Exterior Lines of Tp.2 S., R.35 E., W.M. As surveyed by James P. Currin and James E. Noland, U.S. Deputy Surveyors Under their Special Contract Dated May 4th, 1887.</p>	
	<p>Beginning at the Cor. to Tps. 1 & 2 S., Rs. 34 & 35 E., I run E. on true line on N. Bdy. of Sec. 6, T.2 S., R.35 E. Var. 20°30' E.</p>	
5.20	Canyon, course N.	-300
10.00	Summit, " "	+100
17.50	Canyon, " N.W., water in holes	-300
40.00	<p>Set basalt stone, 9 x 8 x 7 ins., 6 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A fir, 10 ins. diam., brs. S.54°W., 20 lks. dist., No other tree in limits. Pits impracticable. Raised mound of stone around it.</p>	