

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	Timber; scattering pine and fir. Mountainous lands, 59.87 chs. June 29th, 1895.	
	I return to Cor. of Secs. 28, 29, 32 & 33. Thence I run W. on true line bet. Secs. 29 & 32. Ascending on steep rugged point. 11.50 Summit of point, brs. N.W., 800 ft. above creek; descent steep. 16.73 Bottom of ravine, opens N.; ascent 21.17 Intersect U.I.R. line, 3.70 lks. N.20°E. of 55½ Mile Cor., which is a basalt stone, 10 x 10 x 10 in mound of stone I do not find any Closing Cor.. At point of intersection I set a basalt stone, 20 x 10 x 9 ins., 14 ins. in ground, for Closing Cor. of Secs. 29 & 32, marked C.C. on E. face and raise a mound of stone 2 ft. at base, 1½ ft. high, E. of Cor. Pits impracticable. Land; mountainous. Soil; sandy loam, 4th rate. No timber. Mountainous lands, 21.17 chs.	
	From Cor. of Secs. 28, 29, 32 & 33. Thence I run S. on a true line bet. Secs. 32 & 33; ascend steep N. point No timber. 17.50 Top of steep ascent, along rocky ridge, E. of summit. 40.00 Set basalt stone, 21 x 15 x 6 ins., on rock, in mound of stone, marked ¼ on W. face and raised mound of stone 2 ft. at base, 1½ ft. high, W. of Cor. Pits impractic- able. 42.00 Summit of ridge on rock cliff; descend along W. side. 75.03 Intersect S. Bdy. of Tp., 28 chs. W. of Cor. to Secs. 4 & 5 At point of intersection, I Set basalt stone, 22 x 16 x 6 ins., 17 ins. in ground for Closing Cor. of Secs. 32 & 33, marked	