

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	Land; rolling and covered with pine timber and dense thickets of pine, tamarack and spruce undergrowth, 79.00 chs. Soil; 2nd rate.	
	E. on random bet. Secs., 4 & 9. Var. 21° E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
81.40	Intersect N. & S. line, 25 lks. S. of Cor. to Secs. 3, 4, 9 & 10. Thence I run S. 89° 49' W. on true line	
40.70	Set post, 36 x 3 x 3 ins., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A pine, 6 ins. diam., brs. S. 45° E., 32 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 6 ins. diam., brs. N. 20° W., 92 lks. dist., marked $\frac{1}{4}$ S., B.T.	
42.00	Enter opening.	
65.00	Leave opening.	
81.40	To Cor. to Secs. 4, 5, 8 & 9. Land; rolling, covered with heavy pine and tamarack timber Undergrowth of same, 58.40 chs. Soil; 3rd rate. June 29th, 1887.	
	S. bet. Secs. 8 & 9. Var. 21° E.	
40.00	Set post, 36 x 3 x 3 ins., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A pine, 20 ins. in diam., brs. N. 60° E., 239 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 10 ins. diam., brs. S. 8° W., 140 lks. dist., marked $\frac{1}{4}$ S., B.T.	
60.00	Enter pine opening.	
69.00	Draw, course E.	
80.00	Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Cor. to	