

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
20.00	Summit of hill	
40.32	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face, from which, A tamarack, 5 ins. diam., brs. S.50°E., 130 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 16 ins. diam., brs. S., 2 lks. dist., marked $\frac{1}{4}$ S., B.T.	
52.30	Gulch, course N.W.	
80.65	To Cor. to Secs. 8, 9, 16 & 17. Land; rolling. Soil; 3rd rate. Open pine, fir, tamarack timber with huckleberry and snow brush.	
	S. bet Secs. 16 & 17. Var. 20° E.	
32.70	Wagon road, N.W. & S.E.	
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face; raised mound of stone alongside. Pits impracticable.	
44.00	Enter timber and underbrush.	
65.00	Fine opening.	
75.00	Timber and underbrush.	
80.00	Set post, 48 x 4 x 4 ins., 2 ft. in ground for Cor. to Secs. 16, 17, 20 & 21, marked, T.1 S., R.35 E., S.16 on N.E. S.17 on N.W. S.20 on S.W. S.21 on S.E. faces, and 3 notches on S. and 4 notches on E. edges, from which, A fir, 8 ins. diam., brs. N.45°E., 27 lks. dist., marked T.1 S., S.16, B.T. A pine, 24 ins. diam., brs. S.30°E., 35 lks. dist., marked S.21, B.T. A pine, 20 ins. diam., brs. S.70°W., 34 lks. dist., marked R.35 E., S.20, B.T.	