

## Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains	Feet
	Land; rolling. Soil; 2nd rate. Pine and fir timber, open in places. Good pine grass.
	S. bet. Secs. 17 & 18. Var. 22° 15' E.
	Enter pine opening.
40.00	Set post, 36 x 3 x 3 ins., 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on W. face, from which, A pine, 24 ins. diam., brs. S.65°E., 38 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 16 ins. diam., brs. S.85°W., 32 lks. dist., marked $\frac{1}{4}$ S., B.T.
55.00	Enter thick timber.
80.00	Set post, 48 x 4 x 4 ins., 2 ft. in ground, for Cor. to Secs. 17, 18, 19 and 20, marked T.1 S., S.17 on N.E. S.18 on N.W. R.35 E., S.19 on S.W. S.20 on S.E., from which, A fir, 20 ins. diam., brs. N.45°E., 15 lks. dist., marked T.1 S., R.35 E., S.17, B.T. A fir, 16 ins. diam., brs. S.20°E., 15 lks. dist., marked S.20, B.T. A pine, 4 ins. diam., brs. S.60°W., 46 lks. dist., marked S.19, B.T. A pine, 5 ins. diam., brs. N.63°W., 52 lks. dist., marked S.18, B.T.
	Land; rolling, covered with heavy pine, fir and tamarack timber with undergrowth of same, 25.00 chs. Good grass in pine openings, 55.00 chs. Soil; 2nd rate.
	E. on random bet. Secs. 17 & 20. Var. 19° E.
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.

*July 1, 1887*