

Subdivisional Lines, T.1 S., R.35 E., W.M.

Chains		Feet
	on N. face; raised stone mound around it. Pits impracticable.	
47.00	Gulch, course N.W.	150
48.97	Intersect Tp. line 5.98 chs., N. of Cor. to Secs. 25 & 36. Set post, 48 x 4 x 4 ins., 24 ins. in ground, for Closing Cor. to Secs. 30 & 31, marked T.1 S., R.35 E., S.30 on N.E. face S.31 on S.E. R.34 E., S.25 on W. C.C. on E. 1 notch on S. and 5 notches on N. edges, from which, A tamarack, 5 ins. diam., brs. N.45°E., 45 lks. dist., marked T.1 S., S.30, C.C., B.T. A tamarack, 5 ins. diam., brs. S.20°E., 23 lks. dist., marked R.35 E., S.31, C.C., B.T. Land; mountainous, 48.97 chs. Soil; 4th rate. Very little timber or grass.	
	S. on true line bet. Secs. 31 & 32. Var. 19°30' E.	
32.75	Summit of table land; enter timber	1800
40.00	Set post, 36 x 3 x 3 ins., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S on W. face, from which, A pine, 36 ins. diam., brs. N.30°E., 35 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 30 ins. diam., brs. S.45°W., 45 lks. dist., marked $\frac{1}{4}$ S., B.T.	
85.84	Intersect S. Bdy. of Tp., 9.00 chs. E. of $\frac{1}{4}$ Sec. Cor. Set post, 48 x 4 x 4 ins., 2 ft. in ground for Closing Cor. to Secs. 31 & 32, marked T.1 S., S.32 on N.E. R.35 E., S.31 on N.W. T.2 S., S.6 on S. C.C. on N. faces and	