

N. Bdy., T.2 S., R.36 E., W.M.

Chains		Feet
	Tamarack, fir and pine timber with some small openings containing good grass.	
	N.89°58'W. on N. Bdy. of Sec.3. Var.21°45'E.	
40.00	Set pine post, 4 ft. long, 3 ins. thick, 2 ft. in ground for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam., brs.S.54°E.,159 lks. dist. A pine, 20 ins. diam., brs.N.32°W.,113 lks. dist.	100
80.00	Set basalt stone, 18 x 14 x 5, 8 ins. in ground and made stone mound, 2 ft. high for Cor. to Secs. 3, 4, 33 & 34 Land; rolling. Soil; 1st & 3rd rate. Pine, tamarack, fir and spruce timber.	
	N.89°58'W. on N. Bdy. of Sec.4 Var.21°30'E.	
5.00	Old road, course S.20°E.	30
40.00	Set basalt stone, 18 x 14 x 6, 8 ins. in ground for $\frac{1}{4}$ Sec. Cor. A pine, 20 ins. diam., brs. N.10°E.,20 lks. dist. A pine, 36 ins. diam., brs.S.27°E.,45 lks. dist.	30
59.00	Stream, 6 lks. wide, runs S.	140
80.00	Set pine post, 4 ft. long, 4 ins. sq., 2 ft. in ground for Cor. to Secs. 4, 5, 32 & 33. A tamarack, 12 ins. diam., brs.N.30°W., 16 lks. dist. A tamarack, 18 ins. diam., brs.S.34°W.,30 lks. dist. A pine, 18 ins. diam., brs. S.69°E.,13 lks. dist. A tamarack, 24 ins. diam., brs. N.82°E.,35 lks. dist.	1400
	Land; rolling. Soil; 1st & 3rd rate. Pine, tamarack, fir and spruce timber. Some grass.	
	N.89°58'W.on N. Bdy. of Sec.5 Var. 20°00'E.	
5.00	Top of hill.	60