

N. Bdy., T. 2 S., R. 36 E., W.M.

Chains		Feet
40.00	Set pine post, 4 ft. long, 3 ins. thick, 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. A fir, 18 ins. diam., brs. S.25°W., 33 lks. dist. A pine, 8 ins. diam., brs. N.12°W., 82 lks. dist.	50
41.00	Stream, 4 lks. wide, runs S.40°E.	10
80.00	Set basalt stone, 18 x 12 x 3, 8 ins. in ground for Cor. to Secs. 5, 6, 31 & 32. A pine, 7 ins. diam., brs. N.45°E., 3 lks. dist. A pine, 10 ins. diam., brs. N.58°W., 18 lks. dist. A pine, 12 ins. diam., brs. S.52°W., 33 lks. dist. A pine, 8 ins. diam., brs. S.59°E., 21 lks. dist. Land; rolling. Soil; 1st & 3rd rate. Dense groves of black pine, tamarack and fir timber and scattering pine with good grass.	160
	N.89°58'W. on N. Bdy. of Sec.6. Var. 26°20'E.	
27.50	Stage road, course S.60°E.	90
30.50	Stream, 10 lks. wide, runs S.60°E.	20
34.50	Stream, 4 lks. wide, runs N.	5
40.00	Set pine post, 4 ft. long, 3 ins. thick, 2 ft. in ground, for $\frac{1}{4}$ Sec. Cor. A pine, 12 ins. diam., brs. N.42°W., 17 lks. dist. A pine, 15 ins. diam., brs. S.8°E., 49 lks. dist.	5
78.98	To Cor. of T.1 & 2 S. of Rs. 35 & 36 E. Land; rolling. Soil; 1st & 3rd rate. Dense growth of black pine, tamarack, fir and spruce, but little grass. June 15, 1874.	190
	Exteriors of T. 1 S., R. 37 E., W.M. As surveyed by Jacob C. Cooper, U.S. Deputy Surveyor, Under Contract No. 397, Dated July 1, 1881..	
	From the Cor. to Tps. 1 & 2 S., Rs. 36 & 37 E., which is a	