

Exteriors of T.1 S., R.37 E.

Chains		Feet
	<p>1 notch on the S. and 5 notches on N. edges, from which</p> <p>A leaning pine, 8 ins. diam., brs. N.63°W., 43 lks. dist., marked T.1 S., R.36 E., S.25, B.T.</p> <p>A pine, 18 ins. diam., brs. S.80°W., 43 lks. dist., marked T.1 S., R.36 E., S.36, B.T.</p> <p>A pine, 20 ins. diam., brs. S.34°E., 46 lks. dist., marked T.1 S., R.37 E., S.31, B.T.</p> <p>No other trees in limits and raised mound of stone alongside.</p> <p>Land; mountainous and broken.</p> <p>Soil; rocky, 3rd rate.</p> <p>Timber; pine and fir.</p>	
	<p>N. bet. Secs. 25 & 30.</p> <p style="text-align: right;">Var. 20°30'E.</p>	
10.00	Prairie. Descend.	
40.00	<p>Set post, 3½ ft. long, 3 ins. sq., 12 ins. in ground on N. side of head of ravine, in open pine timber for ¼ Sec. Cor., marked ¼ S. on E. and W. face.</p> <p>A pine, 26 ins. diam., brs. N.80°W., 40 lks. dist., marked ¼ S., B.T.</p> <p>A pine, 40 ins. diam., brs. N.10°E., 72 lks. dist., marked ¼ S., B.T.</p>	
	Descend.	
43.00	Bottom of ravine, course W.	
70.50	Ascend abruptly in glade.	
75.00	Cross a gulch in heavy pine timber and underbrush.	
76.00	Ascend abruptly.	
80.00	<p>Set post, 4½ ft. long, 4 ins. sq., 2 ft. in ground on W. side of mountain slope, in dead and fallen timber, 300 ft. below the summit for Cor. to Secs. 19, 24, 25 & 30, marked,</p> <p style="text-align: center;">T.1 S., S.19 on N.E. R.37 E., S.30 on S.E. R.36 E., S.25 on S.W. and</p>	