

Exteriors of T. 1 S.; R.37 E., W.M.

Chains		Feet
	<p>N. on W. Bdy. of Sec. 7.</p> <p style="text-align: right;">Var. 21°30'E. Ascend.</p>	
11.92	<p>The Cor. to Secs. 7, 12, 13 & 18, which is a post, 4½ ft. long, 4 ins. sq., in mound of stone, marked</p> <p style="text-align: center;">T.1 S., S.7 on N.E. R.37 E., S.18 on S.E. R.36 E., S.13 on S.W. and S.12 on N.W., from which;</p> <p>A pine, 28 ins. diam., brs. S.27°W., 66 lks. dist., marked T.1 S., R.36 E., S.13, B.T.</p> <p>Destroyed marks referring to Secs. 7 & 18.</p>	
52.20	The ¼ Sec. Cor.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 6 & 7, marked</p> <p style="text-align: center;">T.1 S., R.37 E. on E. S.6 on N. and S.7 on S. faces, with 5 notches on S. and 1 notch on N. edges, from which;</p> <p>A pine, 12 ins. diam., brs. N.72°E., 47 lks. dist., marked T.1 S., S.6, B.T.</p> <p>A pine, 10 ins. diam., brs. S.58°E., 14 lks. dist., marked R.37 E., S.7, B.T.</p> <p>A fir, 6 ins. diam., brs. N.73°W., 24 lks. dist., marked R.36 E., B.T.</p> <p>Land; mountainous.</p> <p>Soil; 3rd rate.</p> <p>Timber; pine and fir.</p> <p>Undergrowth of fir and pine.</p>	
	<p>N. on W. Bdy. of Sec. 6.</p> <p style="text-align: right;">Var. 20°30'E.</p>	
12.74	<p>The Cor. to Secs. 6, 7, 1 & 12, which is a fir, 5 ins. diam. marked T.1 S., S.6 on N.E.; R.37 E., S.7 on S.E.; R.36 E., S.12 on S.W. and S.1 on N.W. with 5 notches on S. and 1 on N. edges, from which,</p>	