

Subdivisional Lines, T.1 S., R. 36 E., W.M.

Chains		Feet
	N. bet. Secs. 4 & 5.	
	Ascend Var. 21°E.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which,</p> <p>A fir, 6 ins. diam., brs. S.40°E., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.</p> <p>A fir, 10 ins. diam., brs. S.25°W., 7 lks. dist., marked $\frac{1}{4}$ S., B.T.</p>	
75.36	<p>Intersect the Base Line at a point 18.75 chs. E. of Cor. to Secs. 32 & 33, T.1 N., R.36 E.</p> <p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Closing Cor. to Secs. 4 & 5, marked C.C.</p> <p>T.1 S., R.36 E. on S.</p> <p>S.4 on E. and</p> <p>S 5 on W. faces, with</p> <p>4 notches on E. and</p> <p>2 notches on W. edges, from which,</p> <p>A fir, 24 ins. diam., brs. S.32°E., 20 lks. dist., marked T.1 S., R.36 E., S.4, B.T.</p> <p>A fir, 16 ins. diam., brs. S.65°W., 28 lks. dist., marked T.1 S., R.36 E., S.5, B.T.</p> <p>No other tree within limits and raised mound of stone around post.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Timber; scattering pine, fir and tamarack, with dense undergrowth of sage and buck brush.</p>	
	<p>From the Cor. to Secs. 5, 6, 31 & 32 on the S. Bdy., which is a basalt stone, 18 x 12 x 3 ins., marked with 5 notches on E. and 1 notch on W. edges, from which,</p> <p>A pine, 7 ins. diam., brs. N.45°E., 3 lks. dist., marked T.1 S., R.36 E., S.32, B.T.</p> <p>A pine, 10 ins. diam., brs. N.58°W., 18 lks. dist., marked T.1 S., R.36 E., S.31, B.T.</p> <p>A pine, 12 ins. diam., brs. S.52°W., 33 lks. dist.</p>	