

Subdivisional Lines, T.1 S., R.36 E., W.M.

Chains		Feet
	marked T.2 S., R.36 E., S.6, B.T. A pine, 8 ins. diam., brs. S.59°E., 21 lks. dist., marked T.2 S., R.36 E., S.5, B.T.	
	I run N. bet. Secs. 31 & 32 Var. 20°E. Through timber.	
40.00	Set basalt stone, 16 x 10 x 8 ins., 11 ins. in ground for ¼ Sec. Cor., marked ¼ on W. face, from which, A pine, 10 ins. diam., brs. N.30°E., 24 lks. dist., marked ¼ S., B.T. A pine, 10 ins. diam., brs. N.85°W., 19 lks. dist., marked ¼ S., B.T.	
61.50	A wagon road, course E. & W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 29, 30, 31 & 32, marked T.1 S., S.29 on N.E. R.36 E., S.32 on S.E. S.31 on S.W. and S.30 on N.W. faces, with 1 notch on S. and 5 notches on E. edges, from which, A fir, 12 ins. diam., brs. N.30°E., 44 lks. dist., marked T.1 S., R.36 E., S.29, B.T. A fir, 14 ins. diam., brs. S.20°E., 25 lks. dist., marked T.1 S., R.36 E., S.32, B.T. A tamarack, 24 ins. diam., brs. S.35°W., 41 lks. dist., marked T.1 S., R.36 E., S.31, B.T. A fir, 8 ins. diam., brs. N.70°W., 23 lks. dist., marked T.1 S., R.36 E., S.30, B.T.	
	Land; mountainous. Soil; 2nd rate. Heavily timbered with pine, fir and tamarack.	
	Oct. 24, 1882.	