

Exteriors, T.1 S., R.37 E., W.M.

Chains	Feet
	<p>mound of stone around, 3 ft. base, 18 ins. high on S. side of open ridge, for $\frac{1}{2}$ Sec. Cor.; marked $\frac{1}{2}$ S. on N. & S. faces.</p> <p>A pine, 20 ins. diam., brs. S.54°W., 139 lks. dist., marked $\frac{1}{2}$ S., B.T.</p> <p>Descend gradually through open timber.</p>
72.50	Ascend. .Prairie.
88.47	<p>Tps. line, 8.07 chs. S. of Cor. to Tps. 1 & 2 S., Rs. 36 & 37 E., marked,</p> <p>A pine, 8 ins. diam., for Closing Cor.</p> <p>C.C., R.37 E. on E.</p> <p>T.2 S., S.6 on S. and</p> <p>T.1 S., S.31 on N. faces, with</p> <p>6 notches on N.E. & S. faces,</p> <p>A pine, 7 ins. diam., brs. N.70°E., 40 lks. dist., marked T.1 S., R.37 E., S.31, B.T.</p> <p>A pine, 4 ins. diam., brs. S.23°E., 7 lks. dist., marked T.2 S., R.37 E., S.6, B.T.</p>
<p>Subdivisional Lines, T.1 S., R.37 E., W.M. As surveyed by Henry Meldrum, U.S. Deputy Surveyor, Under Contract No. 450, Dated June 11, 1882.</p>	
<p>N. bet. Secs. 25 & 26.</p> <p style="text-align: right;">Var. 24°15'E.</p>	
80.00	<p>*****</p> <p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 23, 24, 25 & 26, marked,</p> <p>T.1 S., S.24 on N.E.</p> <p>R.37 E., S.23 on N.W.</p> <p>S.26 on S.W. and</p> <p>S.25 on S.E. with</p> <p>2 notches on S. and</p> <p>1 notch on E. edges, from which</p> <p>A pine, 15 ins. diam., brs. N.40°W., 39 lks. dist., marked R.37 E., S.23, B.T.</p> <p>A fir, 10 ins. diam., brs. S.73°W., 83 lks. dist.,</p>