

Subdivisional Lines, T. 1 S., R.37 E.,W.M.

Chains	Feet
<p>from which,</p> <p>A fir, 18 ins. diam., brs. S.89°30'W., 20 lks. dist., marked T.1 S.,S.2,B.T.,C.C.</p> <p>A fir, 5 ins. diam., brs. N.20°E.,30 lks. dist., marked T.1 N.,S.36,C.C.,B.T.</p> <p>A pine, 20 ins. diam.,brs. S.77°E., 8 lks. dist., marked R.37 E.,S.1,B.T.,C.C.</p> <p>Timber; fir, pine and tamarack.</p> <p>Undergrowth; fir, pine and willow.</p> <p>Land; mountainous.                      Sept. 21, 1882.</p> <p>Soil; 2nd rate.</p>	<p>*****</p> <p>N. bet. Secs. 26 &amp; 27.</p>
80.00	<p style="text-align: right;">Var. 18°50' E.</p> <p>*****</p> <p>Set post, 4 ft. long, 4 ins. sq.,24 ins. in ground for Cor. to Secs.22, 23, 26 &amp; 27, marked</p> <p style="padding-left: 40px;">T.1 S.,S.23 on N.E.</p> <p style="padding-left: 40px;">R.37 E.,S.22 on N.W.</p> <p style="padding-left: 40px;">S.27 on S.W. and</p> <p style="padding-left: 40px;">S.26 on S.E., with</p> <p style="padding-left: 80px;">2 notches on S. &amp; E. edges,from which,</p> <p>A fir, 7 ins. diam., brs. N.42°E.,36 lks. dist., marked T.1 S.,S.23,B.T.</p> <p>A pine, 18 ins. diam., brs. S.77°E., 8 lks. dist., marked S.26,B.T.</p> <p>A pine, 12 ins. diam., brs.S.43°W., 28 lks. dist., marked S.27,B.T.</p> <p>A pine, 9 ins. diam., brs.N.78°W.,11 lks. dist., marked R.37 E.,S.22,B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p>Dehse pine and fir undergrowth.</p>
<p>E. on random line bet. Secs. 23 &amp; 26.</p> <p style="text-align: right;">Var.27°E.</p>	