

## Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	A fir, 9 ins. diam.; brs. S.34°W., 8 lks. dist., marked S.30, B.T.	
	A pine, 10 ins. diam.; brs. N.63°W., 43 lks. dist., marked R.37 E., S.19, B.T.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with pine, fir and tamarack.	
	Dense undergrowth of pine, fir and willow.	
	<hr/>	
	E. on random line bet. Secs. 20 & 29.	
	Var. 21°E.	
9.60	Ravine, course N.W. Ascend.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor., 150 ft. above Sec. Cor.	
79.80	Intersect N. & S. line; 50 lks. N. of Cor. to Secs. 20, 21, 28 & 29, 400 ft. above $\frac{1}{4}$ Sec. Cor.	
	Thence I run	
	N.89°39' on true line bet. Secs. 20 & 29.	
39.90	Set basalt stone, 17 x 8 x 6 ins., 12 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which;	
	A fir, 9 ins. diam., brs. S.70°E., 23 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	A pine, 4 ins. diam., brs. N.52°E., 22 lks. dist., marked $\frac{1}{4}$ S., B.T.	
79.80	The Cor. to Secs. 19, 20, 29 & 30.	
	Land; mountainous.	
	Soil; good 2nd rate.	
	Heavily timbered with pine, fir and tamarack.	
	Undergrowth of pine, fir.	
	Sept. 27, 1882.	
	<hr/>	
	W. on random line bet. Secs. 19 & 30.	
	Var. 21°E.	
12.25	Ravine, course N.W., 100 ft. deep.	
15.75	Brook, 5 lks. wide in ravine, course N. and ascend hill.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
70.22	Top of Round Butte and descend.	