

Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains	Heavily timbered with pine, fir and tamarack. Dense undergrowth of fir, tamarack and willow. Sept. 28, 1882.	Feet
	N. bet. Secs. 17 & 18.	
	Ascend. Var. 27°E.	
15.00	Top of ridge, brs. N.E. & S.W., 300 ft. high and descend.	
27.00	Ravine, course W., 400 ft. deep and ascend.	
40.00	Set basalt stone, 20 x 15 x 4 ins., 15 ins. in ground for ¼ Sec. Cor., marked ¼ on W. face. No trees in limits & raised mound of stone alongside. Pits impracticable. On top of ridge, brs. N.E. & S.W., 350 ft. above last ravine and gradually descend.	
76.00	Ravine, course W.	
80.00	Set basalt stone, 18 x 12 x 7 ins., 12 ins. in ground for Cor. to Secs. 7, 8, 17 & 18, marked with 4 notches on S. and 5 on E. edges. No trees in limits and raised mound of stone alongside. On steep hillside, 300 ft. above ¼ Sec. Cor.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Scattering pine and fir timber.	
	E. on random line bet. Secs. 8 & 17.	
	Ascend. Var. 20°30'E.	
19.00	Top of hill, brs. N.W. & S.E., 350 ft. above Sec. Cor.	
34.50	Head of ravine, course N.	
40.00	Set temp. ¼ Sec. Cor. Descend hill.	
72.20	Creek, 5 lks. wide, in canyon, runs N., 1000 ft. below ¼ Sec. Cor. and ascend steep hill.	
79.50	Intersect N. & S. line at Cor. to Secs. 8, 9, 17 & 16, 150 ft. above creek.	
	Thence I run	
	W. on true line bet. Secs. 8 & 17.	
39.75	Set basalt stone, 16 x 12 x 10 ins., 11 ins. in ground for ¼ Sec. Cor., marked ¼ on N. face, from which;	