

Subdivisional Lines, T. 2 N., R. 27 E., W. M.

Chains		Feet
80.00	Set post for Cor. to Secs. 13, 14, 11 & 12, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; 3rd rate, producing grass. Land; rolling & descending to the N.	
E. on random line bet. Secs. 12 & 13. <div style="text-align: right;">Var. 19°50'E.</div>		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.50	Intersect E. Bdy. of Tp., 50 lks. S. of Cor. to Secs. 12, 13, 7 & 18, from which Cor., I run S. 89°39' W. on true line bet. Secs. 12 & 13.	
39.75	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.50	The Cor. to Secs. 11, 12, 13 & 14. Soil; 2nd & 3rd rate. Land; rolling.	
N. bet. Secs. 11 & 12.		
17.00	Enter Butter Creek bottom, brs. N.E. & S.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
78.25	Butter Creek (dry), runs N.E.	
80.00	Set post, for Cor. to Secs. 11, 12, 1 & 2, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; on Butter Creek bottom, 1st rate, black loam. Land; level, remainder rolling, 3rd rate.	
E. on random line bet. Secs. 1 & 12. <div style="text-align: right;">Var. 19°45'E.</div>		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.85	Intersect E. Bdy. of Tp., 41 lks. S. of Cor. to Secs. 1, 12, 6 & 7, from which Cor., I run S. 89°42' W. on true line bet. Secs. 1 & 12.	
39.92 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	