

T. 2 N., R. 28 E.

Chains	
	Land, level. Soil, 1st rate.
	N. 89° 30' W., on true line, between secs. 2 and 35. Var. 20° 30' East.
15.00	Indian Trail bears N.E. and S.W.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
80.00	Set post for corner to secs. 2, 3, 34 and 35 in mound of earth &c as per instructions.
	Land, level. Soil, 1st rate. October 3rd, 1859.
	N. 89° 30' W., on true line, between secs. 3 and 34. Var. 20° 15' East.
14.00	Indian Trail bears N. and S.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
80.00	Set post for corner to secs. 3, 4, 33 and 34 in mound of earth &c as per instructions.
	Land, level. Soil, good, 2nd rate.
	N. 89° 30' W., on true line, between secs. 4 and 33. Var. 19° 50' East.
34.00	Indian Trail bears N. and S.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
80.00	Set post for corner to secs. 4, 5, 32 and 33 in mound of earth &c as per instructions.
	Land, level. Soil, good, 2nd rate.
	N. 89° 30' W., on true line, between secs. 5 and 32. Var. 19° 40' East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of earth &c as per instructions.
80.00	Set post for corner to secs. 5, 6, 31 and 32 in mound of earth &c as per instructions.
	Land, level. Soil, 1st rate.