

Subdivisions of T. 2 N., R. 28 E.

Chains	
39.97	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.94	The corner to secs. 27, 28, 33 and 34. Land, hilly. Soil, 2nd rate.
	North between secs. 27 and 28. Var. 20° East. Descend hill.
25.00	Deep Ravine bears E. and W., foot of hill bears E. and W. Ascend hill.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 21, 22, 27 and 28 in mound of stone. Land, hilly. Soil, 2nd rate.
	East on random line between secs. 22 and 27.
40.00	Set temp. $\frac{1}{4}$ sec. corner post.
79.99	Intersect N. and S. line, 70 links North of sec. corner. N. 89° 30' W., on true line, between secs. 22 and 27.
9.40	Indian Trail bears N. and S. Ascend hill.
40.00	Set post for $\frac{1}{2}$ sec. corner in mound of Earth &c as per instructions.
78.50	Top of hill bears N. and S.
79.99	The corner to secs. 21, 22, 27 and 28. Land, steep and broken. Soil, 2nd rate.
	North between secs. 21 and 22. Var. 19° 20' East. Ascend hill.
10.00	Top of hill N. 5 W. S. 5° W.
40.00	Set post for $\frac{1}{2}$ sec. corner in mound of Earth &c as per instructions.