

Subdivisions of T. 2 N., R. 28 E.

Chains	
	Soil, good, 2nd rate.
	North between secs. 8 and 9. Var. 20° East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 4, 5, 8 and 9 in mound of Earth &c as per instructions. Land, level. Soil, good, 2nd rate.
	East on random line between secs. 4 and 9. Var. 19° East.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
80.90	Intersect N. and S. line, 7 links North of sec. corner. N. 89° 57' W., on true line, between secs. 4 and 9.
40.45	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.90	The corner to secs. 4, 5, 8 and 9. Land, gently rolling. Soil, 1st rate.
	North on random line between secs. 4 and 5. Var. 19° East.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
80.80	Intersect North boundary, 42 links East of sec. corner. S. 18° East, on true line, between secs. 4 and 5.
40.80	Set post for $\frac{1}{4}$ sec. corner in mound of Earth.
47.70	Trail bears N.E. and S.W.
80.80	The corner to secs. 4, 5, 8 and 9. Land, gently rolling. Soil, 1st rate. October 8, 1859.
	North between secs. 31 and 32.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per