

Subdivisions of T. 2 N., R. 28 E.

Chains	N. 89° 30' W. on true line, between secs. 20 and 29.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	The corner to secs. 19, 20, 29, and 30. Land, gently rolling. Soil, 1st rate.
	West on random line between secs. 19 and 30.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.00	Intersect West boundary at corner. East on true line between secs. 19 and 30.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	The corner to secs. 19, 20, 29 and 30. Land, gently rolling. Soil, 1st rate.
	North between secs. 19 and 20. Var. 19° 50' East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 17, 18, 19 and 20 in mound of Earth &c as per instructions. Land, level. Soil, 1st rate.
	East on random line between secs. 17 and 20.
40.00	Set post for temp. $\frac{1}{4}$ sec.
79.41	Intersect N. and S. line, 70 links North of sec. corner. N. 89° 30' W., on true line, between secs. 17 and 20.
39.70	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.41	The corner to secs. 17, 18, 19 and 20. Land, gently rolling. Soil, 1st rate.
	October 9, 1859.