

Subdivisions of T. 2 N., R. 28 E.

Chains 79.97	Intersect North boundary, 60 links East of sec. corner. S. 26' East, on true line between secs. 5 and 6.
39.97	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.97	The corner to secs. 5, 6, 7 and 8. Land, level. Soil, 1st rate, sandy. October 10, 1859.
General Description	
The quality of land is gently rolling Prairie (not a tree in the Township) covered with a thick growth of Bunch Grass. There are numerous well springs of clear, fresh water. This Township will amount of a large Settlement.	
T. 1 N., R. 28 E. Surveyed by David P. Thompson, contract No. 83 Dated July 22, 1859.	
North between secs. 1 and 6. *****	
80.00	Set post for corner to Townships Nos. 1 and 2, North of Ranges 27 and 28 East in mound of Earth &c as per instructions.
From the corner to Townships 1 and 2, North of Ranges 27 and 28 East, I run a random line East between said Townships. I find said line to be 5 miles, 79 chains and 25 links, and the falling to be 350 links North of Township corner. The correction for the true line will, therefore, be 75 links East and 58 $\frac{1}{3}$ links North per mile. From the corner to Townships 1 and 2, North of Ranges 28 and 29 East. I run. N. 89° 35' W., on a true line, between secs. 1 and 36. Var. 20° East.	