

## Subdivisions of T. 2 N., R. 29 E.

Chains	Land, gently rolling. Soil, 2nd rate.
	West, on random line, between secs. 19 and 30.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
86.76	Intersect West boundary, 70 links North of sec. corner. N. $89^{\circ} 30'$ East, on true line, between secs. 19 and 30.
17.40	Indian Trail bears N.W. and S.E.
46.76	Set post for $\frac{1}{2}$ sec. corner in mound of Earth &c as per instructions.
86.76	The corner to secs. 19, 20, 29 and 30. Land, gently rolling. Soil, good, 2nd rate.
	North between secs. 19 and 20. Var. $20^{\circ} 15'$ East.
40.00	Set post for $\frac{1}{2}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 17, 18, 19 and 20, in mound of Earth &c as per instructions. Land, gently rolling. Soil, 1st rate.
	East, on a random line, between secs. 17 and 20.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.91	Intersect N. and S. line, 70 links South of corner. S. $89^{\circ} 30'$ W., on true line, between secs. 17 and 20.
39.96	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
63.50	Ravine bears N. and S.
79.91	The corner to secs. 17, 18, 19 and 20. Land, gently rolling. Soil, 1st rate.
	September 9, 1859.
	W., on random line, between secs. 18 and 19.