

Exterior boundaries T. 2, N. R. 30 E.

Chains	
	<p>earth &c., as per instructions. Land, gently rolling. Soil, 2nd rate.</p>
	<p>North between Secs. 19 & 24.</p>
	<p>Variation 18° 05' East.</p>
40.00	<p>Set post for 1/4 Sec. corner in mound of earth with pits, trench &c., as per instructions.</p>
80.00	<p>Set post for corner to Secs. 18, 19, 13 & 24 in mound of earth &c., as per instructions.</p>
	<p>Land, gently rolling.</p>
	<p>Soil, good, 2nd rate.</p>
	<p>North between Secs. 13 & 18.</p>
34.60	<p>Ravine bears N.W. & S.E.</p>
	<p>Variation 19° East.</p>
40.00	<p>Set post for 1/4 Sec. corner in mound of earth &c., as per instructions .</p>
80.00	<p>Set post for corner to Secs. 12, 13, 7 & 18 in mound of earth with pits, trench &c., as per instructions.</p>
	<p>Land, gently rolling, grass prairie.</p>
	<p>Soil, good 2nd rate.</p>
	<p>North between Secs. 7 & 12.</p>
	<p>Variation 18° 15' East.</p>
40.00	<p>Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p>
80.00	<p>Set post for corner to Secs. 6, 7, 1 & 12 in mound of earth with pits, trench &c., as per instructions.</p>
	<p>Land, gently rolling.</p>
	<p>Soil, good 2nd rate.</p>
	<p>August 18th, 1859.</p>