

Subdivisions of T. 2 N. R. 30 E.

Chains	
30.50	Umatilla River 70 links wide, runs N.W.
36.50	Leave bottom, course bears N.W. & S.E.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 1, 2, 11 & 12 in mound of earth &c., as per instructions.
	Land, gently rolling.
	Soil, good 2nd rate.
	Timber on the river, balm.
<hr/>	
	East on a random line between Secs. 1 & 12.
40.00	Set post for temporary 1/4 Sec. corner.
80.40	Intersect East boundary 70 links South of Sec. corner. S. 89° 30' W. on true line between Secs. 1 & 12.
17.50	Enter bottom, bears N. 15' W., S. 15° E.
36.90	Umatilla River 150 links wide runs N. 65° W.
40.20	Set post for 1/4 Sec. corner from which a balm 6 in. diam bears N. 83° E. 24 links dist. " " 5 " " " S. 38° W. 8 " "
	Umatilla River, 150 links wide, runs N.W. & S.E.
61.00	Leaves bottom, bears N.W. & S.E. Ascend hill.
80.40	The corner to Secs. 1, 2, 11 & 12. Land, mostly level, rich bottom. Timber, balm.
<hr/>	
	North on a random line between Secs. 1 & 2. Variation 20° East.
40.00	Set post for temporary 1/4 Sec. corner.
80.00	Intersect North boundary at Sec. corner. South on true line between Secs. 1 & 2.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	The corner to Secs. 1, 2, 11 & 12.