

Subdivisions T. 2 N. R. 30 E.

Chains

Land, gently rolling.

Soil, 2nd rate.

August 29th, 1859.

North between Secs. 34 & 35.

7.50 "Dry Hollow" bears N.W. & East.

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.

80.00 Set post for corner to Secs. 26, 27, 34 & 35 in a mound of earth &c., as per instructions.

Land, level.

Soil, 2nd rate.

East on a random line between Secs. 26 & 35.

40.00 Set post for temp. $\frac{1}{4}$ Sec. corner.

79.67 Intersect N & S line 30 links south of Sec. corner.

S. 89° 46' West on true line between Secs. 26 & 35.

3.17 "Dry Hollow" bears N. 15° E., S. 15° W.

39.83 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.

79.67 The corner to Secs. 26, 27, 34 & 35.

Land, gently rolling.

Soil, 2nd rate.

North between Secs. 26 & 27.

Variation 20° 30' East.

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.

80.00 Set post for corner to Secs. 22, 23, 26 & 27 in mound of earth &c., as per instructions.

Land, gently rolling.

Soil, good 2nd rate.

East on a random line between Secs. 23 & 26.

40.00 Set post for temp. $\frac{1}{4}$ Sec. corner.