

Subdivisions T. 2 N. R. 30 E.

Chains	
79.76	Intersect N & S line 24 links North of Sec. corner. N. 89° 50' W on true line between Secs. 23 & 26.
39.88	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
79.76	The corner to Secs. 22, 23, 26 & 27. Land, gently rolling. Soil, 2nd rate.
	North between Secs. 22 & 23. Variation 20° 20' East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 14, 15, 22 & 23 in mound of earth &c., as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East on a random line between Secs. 14 & 23.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.64	Intersect N & S line 20 links North of Sec. corner. N. 89° 52' W . on true line between Secs. 14 & 23.
39.82	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
60.64	"Dry Hollow" bears N & S.
79.64	The corner to Secs. 14, 15, 22 & 23. Land, gently rolling. Soil, 2nd rate.
	North between Secs. 14 & 15. Variation 19° 30' East.
31.50	"Dry Hollow" bears N. 21° W.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 10, 11, 14 & 15 in mound of earth &c., as per instructions.