

Chains	
	Land, gently rolling. Soil, 2nd rate.
	East on a random line between Secs. 11 & 14.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.96	Intersect N & S line 10 links South of Sec. corner. S. 89° 56' W. on a true line between Secs. 11 & 14.
24.61	Deep ravine bears N & S.
39.98	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
59.96	Summit of hill bears N & S.
79.96	The corner to Secs. 10, 11, 14 & 15 in mound of earth &c., as per instructions.
	Land, gently rolling. Soil, 1st rate.
	North between Secs. 10 & 11. Variation 20° East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
71.75	Enter bottom, bears E & W.
80.00	Set post for corner to Secs. 2, 3, 10 & 11, from which a balm 10 in. diam. bears N. 62 $\frac{1}{2}$ ° W. 24 links dist. " " 6 " " " S. 63° W. 27 " " " willow 4 " " " S. 77° E. 21 " " A thorn 6 " " " N. 78° E. 15 " "
	Land, nearly level. Soil, 1st rate bottom.
	East on a random line between Secs. 2 & 11.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
80.00	Intersect N & S line, 35 links South of Sec. corner. S. 89° 45' W. on true line between Secs. 2 & 11.
10.00	Enter bottom, bears N & S.
12.00	Enter timber.