

Chains	
22.25	River 325 links wide, runs N. 60° E.
40.00	Set post for 1/4 Sec. corner from which a birch 8 in. diam. bears S.50° E.18 links dist. " " 8 " " " N.50° E.18 " "
42.00	Brook, 3 links wide, runs N.E.
48.00	Leave bottom, bears N. 45° W., N. 45° E.
63.25	Enter bottom, bears S. 45° W., N. 45° E.
80.00	The corner to Secs. 2, 3, 10 & 11. Land, level. Soil, 1st rate bottom.
<hr/> North on a random line between Secs. 2 & 3. Variation 19° 30' East.	
40.00	Set post for temporary 1/4 Sec. corner.
79.56	Intersect North boundary, 15 links East of post. S.0° 06' East on true line between Secs. 2 & 3.
39.56	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
64.56	Descend bluff.
69.81	Foot of bluff bears E & W.
72.01	Slough 50 links wide runs west.
70.01	River runs west 1.25 links wide.
79.56	The corner to Secs. 2, 3, 10 & 11. Land, level. Soil, 1st rate.
August 30th, 1859.	
<hr/> North between Secs. 33 & 34.	
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 27, 28, 33 & 34 in mound of earth &c., as per instructions. Land, gently rolling. Soil, 2nd rate.
<hr/> East on a random line between Secs. 27 & 34.	