

## Subdivisions T. 2 N. R. 30 E.

Chains	
	stone.
	Land, rolling.
	Soil, 2nd rate
<hr/>	
	East on random line between Secs. 15 & 22.
40.00	Set post for temp. 1/4 Sec. corner.
80.00	Intersect N. & S line at Sec. corner.
	West on true line between Secs. 15 & 22.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
60.00	Descend hill.
80.00	The corner to Secs. 15, 16, 21 & 22.
	Land, gently rolling.
	Soil, 2nd rate.
<hr/>	
	North between Secs. 15 & 16.
	Variation 20° East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 9, 10, 15 & 16 in mound of stone.
	Land, gently rolling.
	Soil, 2nd rate.
<hr/>	
	East on a random line between Secs. 10 & 15.
40.00	Set post for temp. 1/4 Sec. corner.
80.20	Intersect N & S line 20 links South of Sec. corner.
	S. 89° 51' W on true line between Secs. 10 & 15.
20.00	Dry hollow bears N & S.
40.10	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.20	The corner to Secs. 9, 10, 15 & 16.
	Land, rolling.
	Soil, 2nd rate.