

Subdivisions T. 2 N. R. 30 E.

| | |
|--------|---|
| Chains | |
| 24.50 | Descend hill. |
| 39.54 | Set post for 1/4 Sec. corner in mound of earth &c., as per instructions. |
| 79.54 | The corner to Secs. 3, 4, 9 & 10. Land, level. Soil, 1st rate. August 31st, 1859. |
| <hr/> | |
| | North between Secs. 32 & 33. |
| 40.00 | Set post for 1/4 Sec. corner in mound of earth &c., as per instructions. |
| 55.00 | Ravine bears N. 60° W. |
| 80.00 | Set post for corner to Secs. 28, 29, 32 & 33 in mound of earth &c., as per instructions. Land, rolling. Soil, 2nd rate. |
| <hr/> | |
| | East on a random line between Secs. 28 & 33. |
| 40.00 | Set post for temp. 1/4 Sec. corner. |
| 80.24 | Intersect N & S line 20 links South of corner. S. 89° 51' W. on true line between Secs. 28 & 33. |
| 40.12 | Set post for 1/4 Sec. corner in mound of earth &c., as per instructions. |
| 80.24 | The corner to Secs. 28, 29, 32 & 33. Land, gently rolling. Soil, 1st rate. |
| <hr/> | |
| | North between Secs. 28 & 29. Var. 21° 10' East. |
| 40.00 | Set post for 1/4 Sec. corner in mound of earth &c., as per instructions. |
| 55.00 | Dry Creek bed bears N.W. & S.E. |
| 80.00 | Set post for corner to Secs: 20, 21, 28 & 29 in mound of earth &c., as per instructions. Land, rolling. Soil, 2nd rate. |