

Subdivisions T. 2 N. R. 30 E.

Chains	
	S.89° 59' East on true line between Secs. 19 & 30.
44.88	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
84.88	The corner to Secs. 19, 20, 29 & 30. Land, rolling. Soil, 2nd rate.
<hr/>	
	North between Secs. 19 & 20. Variation 14° 10' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions in Dry Ravine.
41.25	Dry Creek bed bears N.60° W.
80.00	Set post for corner to Secs. 17, 18, 19 & 20 in mound of earth &c., as per instructions. Land, rolling. Soil, 2nd rate.
<hr/>	
	East on random line between Secs. 17 & 20.
40.00	Set post for temp. 1/4 Sec. corner.
80.10	Intersect N & S Line 23 links South of Sec. corner. S.89° 50' W. on true line between Secs. 17 & 20.
40.05	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.10	The corner to Secs. 17, 18, 19 & 20. Land, gently rolling. Soil, good 2nd rate.
<hr/>	
	West on a random line between Secs. 18 & 19.
40.00	Set post for temp. 1/4 Sec. corner.
84.74	Intersect West boundary of Township, 9 links South of Sec. corner. S. 89° 56' E. on true line between Secs. 18 & 19.
44.74	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
84.74	The corner to Secs. 17, 18, 19 & 20.