

Subdivisions T. 2 N. R. 30 E.

Chains	
	Land, broken. Soil, 2nd & 3rd rate.
	North between Secs. 17 & 18. Variation 20° 50' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 7, 8, 17 & 18 in mound of earth &c., as per instructions.
	Land, rolling. Soil, 2nd rate. September 2nd, 1859.
	East on a random line between Secs. 8 & 17.
40.00	Set post for temp. 1/4 Sec. corner.
80.00	Intersect N. & S. Line at Section corner.
	West on true line between Secs. 8 & 17.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
43.00	Ravine bears N & S.
80.00	The corner to Secs. 7, 8, 17 & 18.
	Land, rolling. Soil, 2nd rate.
	West on a random line between Secs. 7 & 18.
40.00	Set post for temp. 1/4 Sec. corner.
85.25	Intersect West boundary 7 links South of Sec. corner. S. 89° 57' East on true line between Secs. 7 & 18.
45.25	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
85.25	The corner to Secs. 7, 8, 17 & 18.
	Land, gently rolling. Soil, 2nd rate.