

Subdivisions, T 2. N. R. 30 E.

Chains

North between Secs. 7 & 8.

Variation 18° 40' East.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

80.00 Set post for corner to Secs. 5, 6, 7 & 8 in mound of earth &c., as per instructions.

Land, rolling.

Soil, 2nd rate.

East on a random line between Secs. 5 & 8.

40.00 Set post for temp. 1/4 Sec. corner.

80.00 Intersect N. & S. Line at Sec. corner.

West on true line between Secs. 5 & 8.

13.00 River bears N. 35° West 150 links wide.

15.00 Slough bears N.W. 50 links wide.

31.00 Leave river bottom steep bluff.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

61.30 Ravine bears N. 30° W.

80.00 The corner to Secs. 5, 6, 7 & 8.

Land, rolling.

Soil, 1st & 2nd rate.

West on random line between Secs. 6 & 7.

40.00 Set post for temp. 1/4 Sec. corner.

85.50 Intersect West boundary 50 links South of Sec. corner.

S. 89° 39' E. on true line between Secs. 6 & 7.

45.50 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.

47.25 Dry Hollow bears N. 20° E & S.

85.50 The corner to Secs. 5, 6, 7 & 8.

Land, rolling.

Soil, 2nd rate.

North on a random line between Secs. 5 & 6.