

S. Bdry, T. 2 N., R. 31 E.

Chains

S. 89° 33' E. on a true line along the North boundary of  
Sec. 1.

Variation 19° 30' E.

13.00 To the bed of a dry ravine, course North. There is a  
beautiful spring in this ravine, about 60 chains South  
of this point, and also one about 40.00 chains North;  
with good, tillable land surrounding.

40.00 Set a post for  $\frac{1}{4}$  Sec. corner. Drove charred stake and  
raised mound with trench, as per instructions.

80.00 The corner to Townships 1 and 2 North, Ranges 31 & 32  
East.

Land, rolling, covered with rich grass.

Soil, sandy.

Oct. 18th, 1860.

E. Bdry, T. 2 N., R. 31 E.

Beginning at the established corner to T. 1 & 2 N., R.  
31 E. & T. 1 & 2, N. R. 32 E.,

Thence

North, along the East boundary of Sec. 36.

Variation 21° 15' E.

40.00 Set a post for  $\frac{1}{4}$  Sec. corner, drove charred stake and  
raised mound, with trench as per instructions.

70.00 To head of dry ravine, course N. E.

80.00 Set post for corner to Secs. 25, 36, 30 & 31, drove  
charred stake and raised mound with trench, as per  
instructions.

Land, rolling grass hills.

Soil, good; 2nd rate.

North on the East boundary of Sec. 25.

Variation 21° 00' E.

40.00 Set a post for  $\frac{1}{4}$  Sec. cor., drove charred stake and  
raised mound, as per instructions.