

Subdivisions, T. 2 N., R. 31 E.

Chains	
	<p>East on a random line between Secs. 25 &amp; 36.                      Variation 17° 30' E.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.84	Intersect East boundary of the Township, 44 links North of the corner to Secs. 25 & 36, from which corner I run N. 89° 41' W. on a true line between Secs. 25 & 36.
39.92	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
71.00	To a dry ravine, course North.
79.84	The corner to Secs. 25 & 26, 35 & 36. Land, gently rolling grass hills. Soil, 2nd rate.
<hr/>	
	North between Secs. 25 and 26.
40.00	Set a post for $\frac{1}{4}$ Sec. cor., drove charred stake and raised mound with trench, as per instructions.
40.20	To a dry ravine, course N. 20° W.
42.50	Foot of stony hill, bears N.20° W. and S.E.
48.00	Enter broken ravines (small), running West.
80.00	Set post in stony ravine for corner to Secs. 23, 24, 25 and 26, and raised stone mound, as per instructions. Land, South half gently rolling; soil, 2nd rate. North half, broken and stony hills.
<hr/>	
	<p>East on a random line between Secs. 24 &amp; 25.                      Variation 20°45' East.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
79.88	Intersect East boundary of Township at the post corner to Secs. 24 & 25, from which corner I run, West on a true line between Secs. 24 & 25.
39.94	Set a post for $\frac{1}{4}$ Sec. cor., drove charred stake and raised mound with trench, as per instructions.
79.88	The corner to Secs. 23, 24, 25 & 26. Land, broken and stony.