

Subdivisions, T.2 N., R. 31 E.

| Chains | |
|--------|---|
| | North between Secs. 23 & 24. |
| 20.00 | Leave stony ravines and enter grass slopes. |
| 40.00 | Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound as per instructions. |
| 80.00 | Set a post for corner to Secs. 13, 14, 23 and 24, and raised stone mound, as per instructions. |
| | Land, good, 2nd rate, except 20.00 chs. South end of line. |
| <hr/> | |
| | East on random line between Secs. 13 & 24. |
| | Variation $18^{\circ} 30'$ East |
| 40.00 | Set temporary $\frac{1}{4}$ Sec. corner. |
| 79.50 | Intersected East boundary of the Township, 12 links North of the corner to Secs. 13 and 24, from which corner I run |
| | N. $89^{\circ} 55'$ W. on a true line between Secs. 13 and 24. |
| 0.50 | Birch Creek, 20 lks. wide (at this time dry), course North |
| 12.00 | Leave Prairie Bottom, bearing N. and S. |
| 15.50 | Mr. Whitney's fence, bearing N & S. |
| 39.75 | Set post for $\frac{1}{4}$ Sec. cor., drove charred stake and raised mound with trench, as per instructions. |
| 79.50 | The corner to Secs. 13, 14, 23 and 24. |
| | Land, gently rolling grass hills, excepting Creek Bottom, which is 1st rate soil. |
| <hr/> | |
| | North between Secs. 13 and 14. |
| 21.50 | Indian Trail, bearing N.W. & S.E. |
| 40.00 | Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound, as per instructions. |
| 47.25 | A bluff, 30 foot high, bearing E & W. |
| 47.50 | Foot of bluff, bearing E & W, and entered Umatilla River bottom. |
| 47.80 | Entered field, bearing E & W. |
| 52.00 | A house bears East 10.00 chs. dist. |