

Subdivisions, T. 2 N., R. 31 E.

Chains	
80.00	Set a post for corner to Secs. 10, 11, 14 and 15. Drove charred stake and raised mound with trench, as per instructions.
	East on random line between Secs. 11 and 14. Variation, 19° 30' East
40.00	Set a temporary $\frac{1}{4}$ Sec. corner.
30.14	Intersected N & S line, 65 links North of the corner to Secs. 11, 12, 13 and 14, from which corner I run, N. 89° 32' W. on a true line between Secs. 11 and 14.
2.75	Right bank of Umatilla River, 75 links wide, runs N. 30° W. Rapid current, low banks.
27.00	Left bank of Umatilla River, 70 links wide, runs S.W. Shallow, rapid current, low banks.
40.07	Set post for $\frac{1}{4}$ Sec. corner, from which A Cottonwood, 14 in. dia. bears N. 75° W. 7 lks. dist. " " 12 " " " S. 7 links distant.
42.00	Foot of bluff and leave river bottom, bearing SW & NE.
53.50	Top of bluff, bearing N.E. and S.W.
57.00	Trail bearing S. & N.W.
80.14	The corner to Secs. 10, 11, 14 and 15. Land, East half, 2d rate bottom land; west half, broken and stony. Timber: Balm and cottonwood.
	North between Secs. 10 & 11.
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
50.75	A trail bearing N.W. & S.E.
80.00	Set a post for corner to Secs. 2, 3, 10 and 11, drove charred stake and raised mound with trench, as per instructions. Land, rolling grass hills. Soil, 2nd rate.