

20

Subdivisions, T.2 N., R. 31 E.

Chains	
	Land, broken grass hills.
	East on random line between Secs. 4 and 9. Variation 17°30' East
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N & S line 35 links North of the corner to Secs. 3, 4, 9 and 10, from which corner I run, N. 89° 45' W. on a true line between Secs. 4 and 9.
6.50	To a deep, dry ravine, course South.
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
80.00	The corner to Secs. 4, 5, 8 and 9. Land, high prairie. Soil, 2nd rate.
	North on a random line between Secs. 4 & 5.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
82.80	Intersected North boundary of Township 170 links East of the corner to Secs. 4 and 5, from which corner I run, S. 1°13' E. on a true line between Secs. 4 and 5.
42.80	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
82.80	The corner to Secs. 4, 5, 8 and 9. Land, rolling table land. Soil, 2nd rate.
	Oct. 24th, 1860.
	North between Secs. 31 & 32. Variation 20°00' East.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound, as per instructions.
73.00	To a ravine, runs N.E.
80.00	Set post for corner to Secs. 29, 30, 31 & 32. Drove charred stake and raised mound with trench, as per instructions.