

Subdivisions, T. 2 N., R. 31 E.

Chains	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N & S line 70 links North of the corner to Secs. 20, 21, 28 and 29, from which corner I run N. 89° 30' West on a true line between Secs. 20 and 29.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.00	The corner to Secs. 19, 20, 29 & 30. Land, broken and stony.
West on a random line between Secs. 19 & 30.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
89.20	Intersected West boundary of Township 139 links South of the corner to Secs. 19 & 30, from which corner I run, S. 89° 01' E. on a true line between Secs. 19 & 30.
49.20	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
89.20	The corner to Secs. 19, 20, 29 & 30. Land, gently rolling. Soil, 2d rate.
North between Secs. 19 & 20.	
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.00	Set a post for corner to Secs. 17, 18, 19 and 20. Drove charred stake and raised stone mound, as per instruc- tions. Land, broken and stony.
East on a random line between Secs. 17 and 20. Variation 21°00' East	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.87	Intersected N & S line 80 links North of the corner to Secs. 16, 17, 20 & 21, from which corner I run N. 89° 25' West on a true line between Secs. 17 & 20.
39.93	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and