

Subdivisions, T. 2 N., R. 31 E.

Chains	
2.50	Right bank Umatilla River, 150 links wide, runs N.W.
39.86	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
77.00	Left bank of Umatilla River, 100 links wide, runs S.W.
79.72	The corner to Secs. 7, 8, 17 & 18.
	Land, level.
	Soil, 1st rate; good for farming purposes.
<hr/> West on random line between Secs. 7 & 18.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
87.00	Intersected West boundary of Township, 250 links South of the corner to Secs. 7 & 18.
	S. 88° 13' E. on a true line between Secs. 7 & 18.
18.00	Enter river bottom, bearing NW & SE.
23.30	Left bank of Umatilla River, 60 links wide, runs NW & S.E.
47.00	Set post for $\frac{1}{4}$ Sec. corner; drove charred stake and raised mound with trench, as per instructions.
52.75	Leave river bottom and enter upland, bearing N.W. & S.E.
87.00	The corner to Secs. 7, 8, 17 and 18.
	Land, 1st and 2d rate soil.
	Timber, Balm Gilliad.
	Undergrowth, briars, willows and vines.
	Note: Dist. of this line 87.00 chains, because of error in Guide Meridian.
<hr/> North between Secs. 7 & 8.	
3.00	Foot of stony hill, bearing E. & W.
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
50.00	Summit of hill, bearing E & W.
80.00	Set a post for corner to Secs. 5, 6, 7 & 8; drove charred stake and raised mound with trench, as per instructions
	Land, broken hills.
	Soil, 2d & 3rd rate.