

Field Notes of the Survey of the  
 Exterior boundaries of T.2 N.R.32 E.  
 Survey by David P. Thompson, under  
 Contract No.106, dated Aug. 16,1864.

| Chains |   |
|--------|---|
|        | North on East boundary of Sec. 36.<br><div style="text-align: right;">Variation 20° East.</div>                             |
| 32.60  | Road bears N.E. & S.W.  |
| 40.00  | Set stone 22 x 8 x 8 in. for $\frac{1}{4}$ Sec. corner.   |
| 80.00  | Set post for corner to Secs. 30, 31, 25 & 36, in mound of earth, with charred stake, pits, trench &c., as per instructions. |
|        | Land, level.  |
|        | Soil, 1st rate.   |
| <hr/>  |   |
|        | North on East boundary of Sec. 25.<br><div style="text-align: right;">Variation 19°45' East</div>                           |
| 40.00  | Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.         |
| 80.00  | Set stone 20 x 12 x 4 in. for corner to Secs. 24, 25, 19 & 30.  |
|        | Land, level.  |
|        | Soil, 1st rate.   |
| <hr/>  |   |
|        | North on East boundary of Sec. 24.<br><div style="text-align: right;">Variation 20° East.</div>                             |
| 40.00  | Set $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits, trench &c., as per instructions.                  |
| 80.00  | Set post for corner to Secs. 18, 19, 13 & 24 in mound of earth, pits, trench &c., as per instructions.                      |
|        | Land, gently rolling.   |
|        | Soil, 1st rate.   |
| <hr/>  |   |
|        | North on East boundary of Sec. 13.<br><div style="text-align: right;">Variation 19°45' East</div>                           |
| 40.00  | Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits, trench &c., as per instructions.        |
| 48.00  | Dry bed of creek, course N.W.   |
|        | Ascend hill.  |
| 65.00  | Top of hill, E & W.   |